

Quotes are valid for 30 days. Major credit cards accepted with a 4% transaction fee. This order is subject to and shall be governed exclusively by GSM's Standard Terms and Conditions, which can be viewed by contacting sales@gsmfiltration.com.

1 of 1



GSM Engineered Fabrics LLC
 2015 Gateway Park Court
 Kingsport TN 37663
 United States
 (423) 348-0954

Quote
 #QUO2496
 6/2/2023

Terms 50% Down, Net 30 on Balance
Lead Time 14-16 Weeks ARO Signed Drawings
Incoterm FOB
Location Kingsport
Sales Rep Bobby Mott
Email bobby@gsmfiltration.com
Shipping Best Way

Notes
Quote for Crossville dewatering cake discharge conveyor system - Freight is PP&Add. OTHER EXCLUSIONS: Installation, foundations, electrical or other service hookup, starters/motors or other instrumentation to control the drive motor, catwalk/stairs or other accessibility features, e-stops/pull cords. All pricing and lead times are subject to design changes, availability and/or escalation of pricing for materials.

Bill To
City of Crossville 392 North Main St Crossville TN 38555-4275 United States

Ship To
City of Crossville 468 Sparta Hwy Crossville TN 38572 United States

Item	Quantity	Rate	Amount
Zinc Epoxy Primer/Top-Coated - Mild Steel Conveyor	1	\$61,025.00	\$61,025.00

24" belt width (BW) x 37 FT long conveyor system to include the following:

- Designed for approx. 50 stph @100 fpm
- All structural components to be mild steel
- Drive - 5HP, 1750 rpm, 230/460VAC, SMR525 w/backstop, v-belts & sheaves, motor mount & torque arm.
- Drive pulley, 12x26, 2-7/16" bearings
- Tail pulley, 12x26, 2-7/16" bearings w/screw take-up, 2' travel, v-plow
- Hopper with skirting
- Uprights & C-channel stringer sections to allow for approx. 20-degree incline
- Channel inset top idlers, CEMA C, 4" OD, 20 degree
- Channel inset return idlers, CEMA C, 4" OD, Flat
- Formed conveyor cover(s) to prevent material contamination
- Belt, 24"W, 2-ply 220 PIW w/mechanical splice

Surface Preparation - SSPC-SP3
 Powder coat to be Zinc Epoxy Primer w/Epoxy Topcoat (overall thickness: 5-6 mils)

Subtotal \$61,025.00
Total \$61,025.00



GSM

Bobby Mott
2015 Gateway Park Ct.
Kingsport, TN 37663
(O) 423-348-0954
(C) 571-214-2027
bobby@gsmfiltration.com
www.gsmfiltration.com



GSM

GSM Engineered Fabrics LLC
2015 Gateway Park Court
Kingsport TN 37663
United States
(423) 348-0954

Quote

#QUO2495

6/2/2023

Terms	50% Down, Net 30 on Balance
Lead Time	14-16 Weeks ARO Signed Drawings
Incoterm	FOB
Location	Kingsport
Sales Rep	Bobby Mott
Email	bobby@gsmfiltration.com
Shipping	Best Way

Notes
Quote for Crossville dewatering cake discharge conveyor system - Freight is PP&Add. OTHER EXCLUSIONS: Installation, foundations, electrical or other service hookup, starters/ motors or other instrumentation to control the drive motor, catwalk/stairs or other accessibility features, e-stops/pull cords. All pricing and lead times are subject to design changes, availability and/or escalation of pricing for materials.

Bill To
City of Crossville 392 North Main St Crossville TN 38555-4275 United States

Ship To
City of Crossville 468 Sparta Hwy Crossville TN 38572 United States

Item	Quantity	Rate	Amount
T-304 Stainless Steel Conveyor	1	\$83,680.00	\$83,680.00

24" belt width (BW) x 37 FT long conveyor system to include the following:

- Designed for approx. 50 stph @100 fpm
- All structural components to be 304SS
- Drive - 5HP, 1750 rpm, 230/460VAC, SMR525 w/backstop, v-belts & sheaves, motor mount & torque arm.
- Drive pulley, 12x26, 2-7/16" bearings
- Tail pulley, 12x26, 2-7/16" bearings w/screw take-up, 2' travel, v-plow
- Hopper with skirting
- Uprights & C-channel stringer sections to allow for approx. 20-degree incline
- Channel inset top idlers, CEMA C, 4" OD, 20 degree
- Channel inset return idlers, CEMA C, 4" OD, Flat
- Formed conveyor cover(s) to prevent material contamination
- Belt, 24"W, 2-ply 220 PIW w/mechanical splice

Subtotal	\$83,680.00
Total	\$83,680.00





