



November 20, 2017

Estimate #8420

Allen
City of Crossville
Crossville, TN

REF: Station Rehab

Allen,

WASCON is pleased to offer the following proposal for you on the above referenced project. Please see the specifics below

1-Lot of Mileage, Labor and Material to Rehab Mocking Bird Pump Station

- (2) MYERS WG30-21 Grinder Pumps
- (2) BERS-0325 H Base 90's
- EP30-21D-FB-C Duplex Control Panel
- (2) BGV200 Bronze Gate Valves
- (2) CIBV200 Ball Check Valves
- 2" SS Piping (Discharge)
- 1" SS Piping (Guide Rails)
- Float Tree and Floats
- Upper and Intermediate Guide Brackets

PRICE: \$15,585.76

NOTES:

1. WASCON standard terms and conditions apply.
2. Freight or any applicable taxes are not included.
3. Quote is valid for 60 days.
4. **If bypass pump is needed we will quote at that time.**
5. **City is responsible for Vacuum Truck and to keep flow off the station if needed.**

If you have any questions please feel free to give me a call.

Thanks,

James Parsons
WASCON Inc.



November 22, 2017

Estimate #8419

Allen
City of Crossville
Crossville, TN

REF: Station Rehab

Allen,

WASCON is pleased to offer the following proposal for you on the above referenced project. Please see the specifics below

1-Lot of Mileage, Labor and Material to Rehab Manchester Pump Station

- (2) 98280863 GRUNDFOS Grinder Pumps SEG.A20.40.2.60M (4HP/3PH/200-230V)
- (2) 98245790 GRUNDFOS 2" Base 90's
- 99107785 GRUNDFOS Duplex Control Panel
- (2) BGV200 Bronze Gate Valves
- (2) CIBV200 Ball Check Valves
- 2" SS Piping (Discharge)
- 1" SS Piping (Guide Rails)
- Float Tree and Floats
- Upper and Intermediate Guide Brackets

PRICE: \$15,238.92


NOTES:

1. WASCON standard terms and conditions apply.
2. Freight or any applicable taxes are not included.
3. Quote is valid for 60 days.
4. **If bypass pump is needed will be quoted at that time.**
5. **City is responsible for Vacuum Truck and to keep flow off the station if needed.**

If you have any questions please feel free to give me a call.

Thanks,

James Parsons
WASCON Inc.



R-W CONTRACTORS, INC.

2511 E. MAIN ST. CHATTANOOGA, TN 37404 VOICE 423/622-1180 FAX 423/622-1189

23Jan18
Veolia Water
Allen Tabor
Mockinbird PS
Phone: 931-484-6257
Email: Kimberly.hinch@veolia.com
Fax: 931-456-6088

Alan,

We are pleased to offer installed equipment:

Pump package supplied by WA Wood Supply with new rail system and 2" stainless piping. We will install new control panel at site

Quote : \$30,544.35

Thanks,



R-W CONTRACTORS, INC.

2511 E. MAIN ST. CHATTANOOGA, TN 37404 VOICE 423/622-1180 FAX 423/622-1189

Lamar Rhoden
Vice President

Ph: 423-622-1180 Cell: 423-595-1076
Fax: 423-622-1189 jlrhoden66@comcast.net



R-W CONTRACTORS, INC.

2511 E. MAIN ST. CHATTANOOGA, TN 37404 VOICE 423/622-1180 FAX 423/622-1189

23Jan18
Veolia Water
Allen Tabor
Manchester Tank PS
Phone: 931-484-6257
Email: Kimberly.hinch@veolia.com
Fax: 931-456-6088

Alan,
We are pleased to offer installed equipment:

Pump package supplied by WA Wood Supply with new rail system and 2" stainless piping. We will install new control panel at site

Quote : \$29,369.85

Thanks,

Jane L. Rhoden



R-W CONTRACTORS, INC.

2511 E. MAIN ST. CHATTANOOGA, TN 37404 VOICE 423/622-1180 FAX 423/622-1189

Lamar Rhoden
Vice President

Ph: 423-622-1180 Cell: 423-595-1076
Fax: 423-622-1189 jlrhoden66@comcast.net



Licensed General Contractor
TN License # 49064

Project Name: Mockingbird and Manchester Sewer Lift Stations Refurbishment
Date: 1/30/2018
Attention: Alan Tabor; Kimberly Hinch; Kimberly.hinch@veolia.com

PCS is pleased to offer the following bid to install piping, fittings, miscellaneous supports and appurtenances per the drawings and specs provided.

Mockingbird Lift Station

Scope of Work

1. Duplex 5hp 240V 1PH replacement grinder pumps and controls
2. All pipe, fittings and valves stainless steel
3. Provide stainless steel drop-in plate with welded studs for new pump base ells to avoid having to puncture fiberglass can base with new fasteners.
4. Replace existing corroded wet well top plate with aluminum top plate with hatch.
5. All guide rails, chains, fasteners and fixtures to be stainless steel or corrosion free.

Lump Sum Bid: Items #1 to #5: \$ 41,400.00

Optional deduct for replacement with 3hp grinder pumps: DEDUCT (\$ 6,400.00)

Manchester Lift Station

Scope of Work

1. Duplex 5hp 240V 3PH replacement grinder pumps and controls
2. All pipe, fittings and valves stainless steel
3. All guide rails, chains, fasteners and fixtures to be stainless steel or corrosion free.

Lump Sum Bid: Items #1 to #3: \$ 38,400.00

Optional deduct for replacement with 4hp grinder pumps: DEDUCT (\$ 5,900.00)

Thank you for your time and consideration. Please contact us at 931-267-6300 if you have any questions.

Respectfully Submitted

Martin Ing

Putnam Contracting Services, LLC

67 N. Washington Avenue, Cookeville TN 38501
Tel: 931 520 7821 Fax: 931 520 7829
Cell: 931 267 6300 Email: martin@pcstn.net